Date: 1/2/2025

Submitted To:

THE COLONY AT WIGGINS BAY 610 WIGGINS BAY DR, NAPLES, FL 34110 C/O PARAMONT PROPERTY



ESTIMATE

ER POOLS INC. Shall provide,

Labor, drain the pool and set hydrostatic pressure. Remove the waterline tile and prep for new tile. Install new tile as needed and install the new depth markers as needed. Prep the surface for new pebble. Lay new pebble. Refill the pool and spa using customer water. Perform a one-time chemical start up.

ESTIMATED LABOR= \$22,000.00

INITIAL HERE

MATERIAL

70 FLORIDA STUCCO SILVER PEARL FINISH @ \$51.29.00 = 3,590.00

12 THINSET @ 38.00 = @ \$456.00

5 GROUT @ 33.00 = \$165.00

1 PEBBLE MAIN DRAIN COVER @ \$70.00 = \$70.00

30 WALL MUD @ \$38.00 = \$1,140.00

70 SQFT WATER LINE TILE (PLEASE NOTE THAT THIS IS A BASE TILE PRICE. IF GLASS

TILE IS CHOSEN, THE PRICE WILL INCREASE.) @ \$48.58 = \$3,400.00

7 NUMBER TILES = \$200.00

2 COMPLETE SKIMMERS (OPTIONAL) = 2,400.00

1 LIGHT = \$1000.00

3 MURIATIC ACID \$20.00 = \$60.00

WATERPROOFING = \$350.00

MISCELLANEOUS NEEDS = \$350.00

CHEMICAL START UP, COST = \$500.00 THIS IS A ONE TIME CHEMICAL STOP, AFTER THE POOL IS FULL. YOUR POOL COMPANY WILL NEED TO START SERVICE OR YOU MAY SIGNUP WITH OUR COMPANY.

DUMP FEE = \$1,000.00

PERMIRT = \$2,000.00

ESTIMATED MATERIAL = \$16,681.00

TOTAL ESTIMATED COST = \$38,681.00

INITIAL HERE

** Cracks or hollow spots are not a part of this estimate and will an added cost if found**

THE ESTIMATE PRICE IS BASED ON CURRENT MATERIAL AND LABOR COST AT THE TIME OF

P.O Box 814 CLEVELAND GA 30528 - INFO@ER-POOLS.COM - OFFICE (239) 403-8069

WHEN THE ESTIMATE WAS WRITTEN. IN THE EVENT THAT MATERIAL OR LABOR COST INCREASE, THE TOTAL ESTIMATE AMOUNT WILL INCREASE.
INITIAL HERE By providing your initials you acknowledge that you understand the information above.
SCOPE OF WORK DOES NOT INCLUDE FENCING OR LANDSCAPING.
50 % DEPOSIT IS REQUIRED UPON SIGNING OF CONTRACT
FINAL CHECK IS DUE UPON COMPLETION OF ALL MAJOR WORK (DECK, PEBBLE WORK, TILE, SCREEN CAGE, COPING); JOB MUST BE PAID IN FULL WITHIN 3 DAYS. NO MONEY CAN BE WITH HELD FOR PUNCH OUT LIST OR BACK-ORDER EQUIPMENT. IN THE EVENT OF EQUIPMENT BEING ON BACK-ORDER, ER POOLS INC. WILL MINUS THE BACK-ORDERED ITEM FROM THE INVOICE UNTIL THEY ARE INSTALLED. CHANGE ORDERS WILL NEED TO BE PAID IN FULL BEFORE INSTALL.
If you want to pay with a credit card a 3.72%, swipe fee will be added to the total amount being paid.
Authorized Signature: Date:
Print name:
Terms & Conditions: A deposit is required to commence, and the balance is due upon completion of all major work (Deck, pebble work, tile, screen cage, coping) ** Cracks or hallow spots are not a part of this estimate and will an added cost if found** THE ESTIMATE PRICE IS BASED ON CURRENT MATERIAL AND LABOR COST AT THE TIME OF WHEN THE ESTIMATE WAS WRITTEN. IN THE EVENT THAT MATERIAL OR LABOR COST INCREASE, THE TOTAL ESTIMATE AMOUNT WILL INCREASE. Any Refund of Deposit will be less, any labor, including office time, any fees incurred, supplies if ordered and not able to be returned, re-stocking fees and cost to send back check by certified mail. Sample board is just an idea of the product, the stucco is mixed by man and put on by hand, and small imperfections may be seen. NATURAL STONE HAS IMPERFECTIONS WE CAN NOT CONTROL. The signing of this document constitutes an agreement based on the estimate and the owner has been informed the prices may change. The owner will be notified in advance as the supplies inform us, as the markets continue to change. The goods sold remain the property of ER Pools INC. until paid in full. We have the right to come on the property to remove at any time if not paid, INITIAL HERE
Warranties: 10 YEARS RESIDENTIAL, 3 YEARS COMMERCIAL MANUFACTURE WARRANTY APPLIES TO ALL MATERIAL THROUGH FLORIDA STUCCO. ER POOLS GIVES 1 YEAR ON ALL LABOR, IF THE POOL AND SPA ARE MAINTAINED BY ER POOLS. INITIAL HERE